

A

[1]

Connection to existing pipe to be checked on site
For installation tolerances dimensions to be checked by pipe contractor at site.
Degree of prefabrication to be decided by contractor.

Welding factor	Acc. to pipe class
----------------	--------------------

Directive	2014/68/EU	Pipe Class	/I19440-VE16C1C-R00
Design press. (min)	-1bar	PED Category	I
Design temp. (min)	-	Media	
Max. allow. press. (PS)	-	Standard	
Operating press.	5bar	P&ID	RAU8F00303
Operating temp.	159degC	Design press.	6bar
PED Module	-	Design temp.	220degC
PED Group	-	Test press.	-
Wind loads	-	Pipe list doc. ID	RAUAF04300
External loads	-	Valve list doc. ID	RAUAF04301



